



MOBILE BATCHING PLANT

Description

A plant for 'Africa'. A robust and practical plant for use by any workforce with optional automated stages to increase productivity and output.

Specifications

8 cbm hopper mounted with load cells on mobile 6.5t axel frame with a 12.m belt conveyor system driven by a 5.5kw Bonfiglioli electric motor with a mounted gearbox.

Includes

Rear mounted cement bag splitter Manual discharging doors Water Meter Electronic control box

Static Data

Production Output	Drop Qty
Wet concrete per hour	25m³

* Production output may vary from area to area and operating conditions. Should be used as a target estimate only.

2 - 3

Labour Force

Power Requirements	Phase	kVA	Amps
Mobile Batching plant	3 Phase	11.5	20

Optional Extras (Semi Automation)

- 1. Generator
- Self priming water pump 220v
- 3. Pneumatically operated discharge door handling